

# Accelerator for medical applications – CAS'15

## CAS Working group #2

Jenny Dueck (PSI)

Sejla Mizic-Bajric (MedAustron)

Dr. Viktor Iakovenko (Kiev Institute for Nuclear Research)

Luis Mora Vallejo (CERN)

Dr. Xander Janssen (VDL)

Stefano Benedetti (CERN)

# Introduction

- We have chosen Canada as the country for our hadron therapy facility
- We propose a facility for both *carbon ion and proton* therapy. Other ion species, with  $Q/m=1/2$  (or “slightly” different, i.e. C11) could be used as well
- The accelerator technology that we propose is a *full linear solution*
- Given the absence of an available commercial facility, we propose a 2 years-long design study (same scheme of the *PIMMS study*), at the end of which a committee will decide whether to turn into construction phase or to stop the project
- Budget has to be allocated for the design study (see dedicated slide)



## MAPLE

**Medical Accelerator for Protons and  
Light ions for Extinction of cancer**



# Number of patients



Total population 36.16M

62% South-East Ontario  
South Quebec 22.4M

1% Cancer patient 224k

20% Radio therapy 44.8k

15% Hadron therapy 7k




GPTC (NL) 600 p/y  
Scandion clinic (SE) 1000 p/y  
MedAustron (A) 1400 p/y


|       |                  |
|-------|------------------|
| 5     | min/fraction     |
| 12    | fraction/hour    |
| 12    | hours/day        |
| 144   | fraction/day     |
| 250   | days/year        |
| 36000 | fraction/year    |
| 20    | fraction/patient |
| 1800  | patients/year    |

# Rationale of a full linear solution


- BEAM ENERGY. Can be varied actively, at the machine level, from pulse to pulse. 200 Hz repetition rate is doable.
- BEAM QUALITY. No need of degraders, i.e. no beam size spreading.
- COST-EFFECTIVE SOLUTION. A 3-room facility (without gantries) would cost around 40 M€ (source: ADAM)
- COMPACT SOLUTION. Bottom right picture has the footprint of CNAO.



# Main design parameters



- Final beam energy: 450 MeV/u
- Energy variation range:  
70 MeV/u – 450 MeV/u
- Average beam intensity:  
1-2 nA
- Spot size:  
FWHM adjustable 4 mm – 12 mm
- Field size: 30 x 30 cm
- Active scanning,  
energy adjustable each 5 ms



# Technical specifications

- ION SOURCE. EBIS type. High frequency intense pulsed C6+ and other species. Repetition rate (eventually with two sources) up to 400 Hz. Pulse length: 5  $\mu$ s. Number of ions per  $\mu$ s:  $2e+8$ . Pulse stability: <5%. Beam emittance: 0.1 to 0.2 mm.mrad.
- INJECTOR. RFQ. Frequency: 750 MHz. Input energy: 20 KeV/u. Output energy: 2.5 MeV/u. Transmission: >95%.
- INTERMEDIATE  $\beta$  STRUCTURE. IH type. Frequency: 3 GHz. Output energy: 70 MeV/u. Transmission: >15%. FODO lattice: PMQs.
- HIGH  $\beta$  STRUCTURE. CCL type. Frequency: 3 GHz. Output energy: 450 MeV/u. Transmission: >95%. FODO lattice: PMQs.
- Transfer lines: 180° MEBT with two 90° SC (?) dipoles and quadrupole in between to close dispersion. HEBT. Straight HEBT à la MedAustron.

# RF power consumption estimation $\Delta W = \sqrt{Z} \uparrow$ *LP*

CCL:

- Delta energy gain = 450 MeV/u – 70 MeV/u = 380 MeV/u = 760 MeV
- Approx. length = 35 m
- Avg Shunt Impedance= 100 Mohm/m
- Peak power: 165 MW ish... -> Avg. gradient 22 MV/m

H-structure:

- Delta energy gain = 70 MeV/u – 2.5 MeV/u = 67.5 MeV/u = 135 MeV
- Approx. length = 15 m
- Avg Shunt Impedance= 60 Mohm/m
- Peak power: 20 MW ish... -> Avg. gradient 10 MV/m

Total RF peak power ( with 1 MW RFQ) = 186 MW (225 with 20% wg losses)

D.C. = 4  $\mu$ s x 400 Hz = 1.6e-3

**Average RF power consumption = 360 kW**



# RF power source



THALES TH 2157

K1 ScandiNova modulator

M3 ScandiNova modulator



KIU-147/BAC

No oil tank.  
Possibility to operate klystron at a distance.

|                   |        |            |       |
|-------------------|--------|------------|-------|
| Frequency range   | 2998.5 |            | MHz   |
| RF output power   |        |            |       |
| • peak            | 7.5    | <b>7.7</b> | MW    |
| • average         | 8      | <b>30</b>  | kW    |
| RF pulse duration | 6      | <b>6</b>   | μ sec |
| Saturated gain    | 48     | <b>51</b>  | dB    |
| Efficiency        | 48     | <b>77</b>  | %     |


## Electrical characteristics

|                 |     |            |    |
|-----------------|-----|------------|----|
| Cathode voltage | 150 | <b>52</b>  | kV |
| Beam current    | 105 | <b>195</b> | A  |

No focusing solenoid (3 kW)  
Weight 90 kg  
Length 0.90 m



# Timeline and business plan

| 1            |    |    |    | 2  |    |    |    | 3            |    |    |    | 4                        |    |    |    | 5  |    |    |    | 6                  |    |    |    | 7                |    |    |    |   |  |  |  |
|--------------|----|----|----|----|----|----|----|--------------|----|----|----|--------------------------|----|----|----|----|----|----|----|--------------------|----|----|----|------------------|----|----|----|---|--|--|--|
| Q1           | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1           | Q2 | Q3 | Q4 | Q1                       | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1                 | Q2 | Q3 | Q4 | Q1               | Q2 | Q3 | Q4 |   |  |  |  |
| Design Study |    |    |    |    |    |    |    |              |    |    |    |                          |    |    |    |    |    |    |    |                    |    |    |    |                  |    |    |    |   |  |  |  |
|              |    |    |    |    |    |    |    | Construction |    |    |    |                          |    |    |    |    |    |    |    |                    |    |    |    |                  |    |    |    |   |  |  |  |
|              |    |    |    |    |    |    |    |              |    |    |    | Accelerator Installation |    |    |    |    |    |    |    |                    |    |    |    |                  |    |    |    |   |  |  |  |
|              |    |    |    |    |    |    |    |              |    |    |    |                          |    |    |    |    |    |    |    | Beam commissioning |    |    |    |                  |    |    |    |   |  |  |  |
|              |    |    |    |    |    |    |    |              |    |    |    |                          |    |    |    |    |    |    |    |                    |    |    |    | Acceptance tests |    |    |    |  |  |  |  |

| Total costs   |              |   |
|---|--------------|---|
| Fixed   |              | Variable/running                                |
| - Ground (3 ha)   | 15           | - Maintenance / consumables 6                   |
| - Building  | 20           | - Energy (2MW x 16h/d) 1                        |
| - Accelerator   | 25           | - Personnel (120 persons) 8                     |
| - 2x Gantry   | 20           | - Patient hotel (100 patients for 250 days) 2.5 |
| - Commissioning incl personnel                                  | 10           |   |
| - Treatment planning  | 7            |   |
| - Patient positioning   | 10           |   |
| - Imaging systems (1 MRI, CT, 1 PET-CT, 4 CBCT)                 | 2            |   |
| - Permits   | 1.5          |   |
| <b>- Decomissioning including removal of activated material</b> | <b>???</b>   |   |
| A Brahme et al. Nucl. Instr. And Meth. In Phys. Res. B          |              |   |
| <b>Sum</b>  | <b>110.5</b> | <b>17.5</b>                                     |

| Total income |                             |
|--------------|-----------------------------|
| Fixed        | Variable/running            |
|              | - 1800 patients x 20.000 36 |

# Expertise needed

- BOARD
- HR
- Radioprotection
- FDA certifications and quality
- Safety
- Clinical Dep.
- Radiotherapy Dep.
- Medical Physics Dep.
- Imaging Dep.
- Radiobiology Dep.
- Bioengineering Dep.
- Administrative Dep.
- Finance Dep.
- Infrastructure Dep. (Electr, Mech, IT...)
- Accelerator Dep.
- R&D Dep.
- Operation Dep.
- Maintenance Dep.

**Around 120 FTE (Full Time Equivalent) needed**

# Process map

