| Commissioning Strategies | |
|--|--|
| CERN School on High Power Hadron Machines | |
| Bilbao Spain, 24 May – 2 June, 2011 | |
| J. Galambos | |

| Commissionii | ng Phases | |
|---|--------------------|---------------------------------------|
| Equipment testin Individual equips Systems Integration | g nent | |
| The first beam Initial "beam pul 1st order problen Simple tools nee | ling" ns ded | |
| Intensity increase, power rampup, … – 2nd order problems – More sophisticated diagnostics required | | |
| 2 Managed by UT-Battelle for the U.S. Department of Energy | Presentation_name | CAK <u>RIDGE</u> Verbuildcorrep |

<section-header> Pre-Beam Tasks Hardware tests Systems tested independently Quad polarity test Quad polarity test Soci test of minimal integration (vacuum, LLRF, high power RF, cooling, controls, ...) Good opportunity to get to know your equipment Software tests Virtual accelerator Sem simulations When will the beam debunch, can detectors measure it? Simulations form the basis of the commissioning plan

"First Beam" Tasks

- General advice:
 - Don't trust any measurements
 If an instrument indicates no beam, cross check
- Get the beam down the pipe
- Calibrate loss monitors
 - Use controlled beam spills
 - Test machine protection systems
- Use the most simple direct measurements
 - Beam loss
 - Current monitors
 - Beam Position Monitors (BPM)

4 Managed by UT-Battelle for the U.S. Department of Energy

Presentation_name























































Commissioning: A Period of Ups and Downs

- Beam commissioning can be extremely frustrating and is hard work (long hours)
- But is is ultimately extremely rewarding
- Enjoy it

















