

# The real “life” of operation

V. Baglin

CERN TE-VSC, Geneva



# Introduction

- Your beautiful and expensive vacuum system was well designed and prototypes deeply tested ...

... so what can happen?

# First turns of LHC: 10 Sept 2008




# The real life of operation ...

Roger Bailey  
Operation SL

C. Llewellyn Smith  
CERN DG  
1994-1998

L. Maiani  
CERN DG  
1999-2003



R. Aymar  
CERN DG  
2004-2008

E. Schopper  
CERN DG  
1981-1988

C. Rubbia  
CERN DG  
1989-1993



Roger Bailey  
Operation GL

# The real life of operation ...



Roger Bailey  
Operation SL




Dr Lynn Evans CBE, LHC Project Leader and Roger Bailey, Operation Group LHC Section Leader inspecting part of the LHC tunnel in December 2006 © STFC



Lynn Evans  
LHC PL



# What about the real life through the looking glass?




# The Sector 3-4 incident (just before the 1st ramp)

19<sup>th</sup> September 2008 at 11:18.36

last test of the last sector: 7kA (4TeV) towards 9.3 kA (5TeV)

**Electrical arc** at 8.7 kA in the interconnection

Rupture of bellows, expansion of liquid Helium with superinsulation debris




# 2009 - overall repair and consolidation

14 quadrupole magnets replaced

39 dipole magnets replaced

204 interconnections repaired

5km beam-tube cleaned



longitudinal restraining system quadrupoles

900 ports for helium pressure release

6500 new detectors and 250km cables for new Interconnect Protection System

collateral damage mitigation



# Impact on beam tube ...

- 2x 2.8 km damaged

Clean Copper surface.

Contamination with multi-layer magnet insulation debris.


Contamination with soot.



≈ 60% of the chambers

≈ 20% of the chambers

# TE-VSC Vacuum Cleaner



Credits: E. Mahner, B. Jenninger, B. Henrist

# Beams back: 20 Nov 2009

Roger still here!  
Happier than ever!



# 1. What can happen?

# Disclaimer


- What I will show is **not an exhaustive list** of the events which can happen ...
- I really trust the **creativity** of nature and humanity to complete the list!

# 1.1 Vacuum loss

# Leaks

- This is the **first demon** faced by the vacuum expert
- Leaks can be due to:
  - installations non conformity
  - bad design / material
  - mechanical or thermal fatigue of a component
  - corrosion
  - ...
- One great thing, **if you don't look for them**, you might not find them yourself ....

... but something else might find it for you!





He leak detector

See tutorial P. Cruikshank, G. Bregliozzi

# Leak at welds: mechanical analysis


- The **stress** at the level of the weld increases under vacuum and weight (and thermal stress)
- Example of SuperKEKB:
  - Supporting of below before evacuation
  - Rewelding if too thin thickness



Y. Suetsugu *et al.* J. Vac. Sci. Technol. A 34, 021605 (2016)


# LHC: 1<sup>st</sup> Leak triggering a beam dump

- During operation, the bellow of a wire scanner broke, creating a leak
  - The total amount of bellow's cycle was **not recorded** since the start of LHC and overpassed by far the acceptable limit ;-)
- Varnished was applied without success
- The **emergency procedure** which consist in Ne venting allowed to replace the faulty component and resume beam operation after 2 days



# Fast Repair: Ne venting



- 5 days intervention
- Ne flow to reduce air back streaming
- This method avoids the NEG saturation (remember Ne is an inert gas)
- Avoid major NEG saturation but possible local saturation close to the exchanged piece
- Zone that can stand over pressurization +100mbar



Neon trolley

# Corrosion




- Originates from **chlorine** pitting
- ISR: **Brazing flux** ! ( $\text{ZnCl}_2$ )
- SPS: fire detection **PVC** pipes subjected to radiation in a wet environment and located above the vacuum system
- LEP: **PVC** based tape wrapped around photomultipliers



See S. Sgobba, F. Cerutti, M. Brugger lectures

# Corrosion

- **Brazing flux** containing chlorine leads to corrosion.
- Example, ESRF



The chlorine cannot be cleaned  
being trapped in small interstices!  
Brazing flux forbidden!




L. Hardy, ARW 2009

# Water leak in cooled devices

- The crotch is a **photon absorber** (~ kw), used in SR machines. It need to be water cooled ...
- Example ESRF crotch, March 2005

- **Water leak:**

- 50 m vented
- water inside the vacuum system!
- 5 days lost



L. Hardy, ARW 2009

Origin: de-ionised water+ Copper + radiations

# Water – cooled devices: another example

- Example Spring 8 photon absorber, June 2001
  - ➔ New design with cooling tube out of the SR fan








Fig. 5. Photographs of the cross section of the photon absorber removed from the RF cavity (a) and the cross section of the eroded part (b). Corrosion was found only inside the water pipe where the synchrotron radiation hits.

M. Shoji *et al.*  
 Vacuum 84 (2010) 738–742




# 1.2 Non conformities

# LHC Dipole-Dipole Interconnection




# Plug-in Modules with RF Fingers

- Last installed component to **interconnect** superconducting magnets (~ 1 700 PIM)
- **RF bridge** made of sliding RF fingers (Au coated to avoid cold welding)
- < 0.1 mOhm contact resistance, Rh coating (i.e. 3 mOhm/RF finger)



Room temperature position



Courtesy R. Veness

Working position at cryogenic temperature

# August 2007



- After warm-up of sector 7-8
  - A **buckled** PIM was discovered in interconnect QQBI.26.R7
  - Was really found by chance!



# Why buckling ?

- Non conformity during manufacturing
- Not properly documented => Lesson: respect of Quality Assurance is a MUST

## QQBI.26R7 V1 bending angles out of tolerance





# Deformation of bellows

- Production of bellows for the LHC QRL:
  - design: convolution height “at the limit”
  - non-conform production
  - not traced !
  
- Cured by mechanical consolidation
- Production follow-up shall be appropriate !




See C. Garion lecture and tutorial

# It can always be worse ..



- CERN ISR vacuum chamber located at the interaction point

## Imploded Thin Walled Vacuum Chamber




# 1.3 Aperture losses

# Warm Modules for Interconnection




- Modular system
- ~ 1 800 in the LHC ring
- Bellow shielding to optimise beam impedance
- RF bridge with several shapes (circular/elliptical)
- Ag coated CuBe fingers
- Rh coated insert
- Allow thermal expansion during bakeout (+/- 20 mm stroke)
- Can accommodate instrumentation ports



See R. Wanzenberg, B. Salvant, S. Calatroni lecture and tutorial

# Summer 2011 : Vacuum Modules - VMTSA

- Design extrapolated and **not mechanically validated** before installation in the ring
- **Pressure spikes** located beside inner triplets generated interlocks and background



Observed Pressure spikes during a physics fill

# Vacuum Modules : VMTSA - 2011

- X-rays done in May showed a conform module, in November the module was broken
- The RF bridge was **destroyed by the beam !**
- 8 out of a total of 20 in LHC **were damaged i.e. 40 %**

## Typical default, DCUM 3259.3524

### Left side

Side view (xray from corridor to QRL)


b) Metallic noise due to loose spring when hitting vacuum chamber

c) RF fingers falling due to broken spring

d) aperture reduced ?

### Non Conform

**Spring was broken between May and November 2011**



# Heating due to $\text{Re}[Z]$




- Origin of the systematic default was identified to be due to a **poor contact** between the RF finger and the transition tube.
- Lesson : always **validate the design** of your components (**even under schedule pressure**)


See R. Wanzenberg, B. Salvant and S. Calatroni lecture and tutorial

# 2011: Pressure spikes in right side of CMS

- In 2011, frequent pressure spikes, some up to  $10^{-6}$  mbar, were observed at CMS, 18 m, right side.
- When the local pressure was above  $10^{-8}$  mbar, CMS background was larger than 100 % thereby reducing the detector capability




Typical Observation



Courtesy J-M. Dalin EN-MME

# Ne venting to save the 2012 CMS Run !

- Vacuum system performance recovered even following the dismantling of 2 m long vacuum chambers



**CMS**

16 m & 18 m flanges were opened while Ne flushing

Forward chamber

Ne

Air

October 18th, 2012




3rd Vacuum Symposium UK



January 2012

# 4<sup>th</sup> July 2012: SM BEH Boson Discovery




ATLAS and CMS discovered a new boson in the mass region  $\sim 125\text{-}126 \text{ GeV}/c^2$



# RF bridge: PETRA III

- PETRA III RF contact are placed inside the transition tube when the bellow are over-extended
  - => **beam intensity limited** in 40 bunch modes to 80 mA till 2012 (design 100 mA)
- Define specification
- Check at surface mechanical and electrical specification

## RF-Contacts in RF-shielded Bellows



Courtesy L. Lilje





L. Lilje | Accelerator vacuum systems at DESY | 1.4.2014 | Page 9



# RF bridge: ESRF

- Vacuum levels and gamma-graphy are great tools to avoid disaster.
- X-rays before machine closure and pressure follow up helps!



# RF Contact: SOLEIL


- Misplaced RF contact are producing **arcing**



N. Bechu, OLOAV 2014

# RF bridge: RHIC

## RF finger repair at RHIC




P. Sampson, ARW2009

# RF bridge: BEPC II



J, Cao, ARW2013

# RF Bridge: KEKB




M. Mazuzawa, 2004

# Beam induced outgassing


- A movable mask to protect ALICE during injection (Boron nitride jaw)
- Deformed beam screen observed during winter technical stop 2011-12

- Suspected origin is a **bad sliding point**
- Cu beam screen was **deformed** during bakeout at 300 deg




- Beam induced, via impedance, **thermal outgassing**

- $\sim 10^{-7}$  mbar



# Benefit of a large aperture

- **Allows many optics to be deployed**, in particular new ones not foreseen at the stage of the design e.g.
  - CERN Achromatic Telescope Squeeze to be used for HL-LHC
  - PETRA III
- Solving ULO (unidentified lying object) issue by applying a bump



CERN ULO 15R8

### “Stichabsorber“

- > Lesson learned (again)
  - Beam physicist says: „Beam will always be in nominal orbit.“
  - Engineer optimises for lowest power deposition
  - Shallow angle solution
  - Commissioning will prove physicist wrong
  - Mike Seidel in OLAV1 2005
  - “→ build your system passively safe if possible; any orbit that circulates will occur!”


L. Lijje | Accelerator vacuum systems at DE



L. Lutz, Olav 2014

# Unexpected beam aperture restriction in LEP around IP1 22 June 1996

Could not get the beam to circulate more than 15 turns even with large bumps all around the ring. Use single turn orbit system and normalised the measurement.



Single Turn  
Stopper


positrons →

QL10.L1


S. Myers

# Unexpected beam aperture restriction in LEP around IP1 22 June 1996

Zoom in on Quadrupole



10 metres to the right





- Qualified by of the CERN accelerator director, S. Myers, of:

**Unsociable sabotage: both bottles were empty!!**



# 1.4 Energy losses

# Tunnel environment and cleanliness ...



# UFO Particulates


- They **originate** from the construction / installation and may latter interact with the beams
- Most of the particulates have a positive charge (shall be less sensitive to positive beams)
- HERA
  - pumping system upgraded to **NEG strip** and **positron operation** preferred
- LHC
  - Most of them are very small, a few leads to beam dump triggered by BLM system
  - **Rate reduce** with time thanks to gravity and vibrations.



See lecture L. Lilje

# Stored Energy

- Modern machines have a few MJ of energy ... what can you do with that apart from collision ?




courtesy R.Assmann

See F. Cerutti, M. Brugger lectures


# Beam extraction from SPS: 10/2004

- 450 GeV beam,  $3.4 \cdot 10^{13}$  p on stainless steel (3 MJ) miskicked, result:  
→ A 1 m long groove along a SPS vacuum chamber after the impact of ~1% of a nominal LHC beam during an 'incident': ~ 3 days repair
- In a superconducting machine, it would cost several months of work!




# TEVATRON Accident: 5 December 2003

- A roman pot moved into the beam
  - the particle showers quenched 16 superconducting magnets
- The beam moved by 0.005 mm/turn and touched a collimator jaw surface after ~ 300 turns
  - the entire beam was lost, mostly at the collimator
- Beam loss monitor where switched off!
- 10 days repair



5 mm hole in a vertical W jaw



25 cm groove in stainless steel

# Also with electrons machine

- Example of an air leak in SPRING 8:
  - 8 GeV electron beam with 15 micron vertical beam size on a 0.7 mm thick stainless steel wall




Fig. 6. Cross section of the injection chamber wall at the broken part. It seems that the electron beam hits the thin wall several times, since many traces of electron beam bombardment were found.

M. Shoji *et al.*

Vacuum 84 (2010) 738–742

# Also with photons from SR machine

- Example of melted gate valve at SSRF, Shanghai:
  - The photon shutter was opened while the gate valve was closed, the synchrotron radiation produced by 3.5 GeV electron beam at 200 mA melted the stainless steel.




**Metal melted by SR heat load**

L. Yin, ARW2013

# Also with photons from SR machine

- Example of SOLEIL, france




**Metal melted by SR  
heat load**



Courtesy N. Bechu

# SR induced fluorescence

- Observed at SOLEIL, france
- The X-ray fluorescence of Zr at 16 and 18 keV can **destroy the Kapton bakeout foil** if the Al or Cu vacuum chamber is thick enough



C. Herbeaux, OLAV 2014

# The read pressure is not always a true pressure

- Photons produce photoelectrons, stray particles can ionised the cable or magnetic field can modified significantly the reading of pressure

The apparent absence of beam conditioning is due to scattered particles on the gauge collector and cable






Fig. 2. Normalized pressure rise and beam lifetime as a function of beam dose. Pressure rise is the difference between beam-on and beam-off pressure.

M. Shoji *et al.*  
 Vacuum 84 (2010) 738–742

Erratic pressure readings



L. Hardy, ARW 2009  
 See F. Cerutti and M. Brugger lectures


# 1.5 Summary

# Summary

- The vacuum group people have always the impression of being firemen !!!!!



- Can we do better?



Those who cannot  
remember the past  
are condemned to  
repeat it.


George Santayana

## 2. Quest towards availability

# Availability: Vad fan är det här? (what the hell is this?)



**Availability:** The percentage of time an equipment is in operable state

# Accelerator schedule: objective beam time!



5640 hours USM  
1294 hours MDIT  
1824 hours Shutdown


1885 hours end/ PSS  
4125 hours updated by LH on 14-08-2009 (V1)  
608.0 hours updated by PE on 28-08-2009 (V1)



Technical Stop  
Recommissioning with beam  
Scrubbing (indicative - dates to be established)

Machine development  
Special physics runs (indicative - schedule to be established)

SSRF Operation Schedule (Jan 1 - Dec 31, 2012)



U User Time  
A Machine Study  
B Beamline Study  
M Maintenance, no beam  
D Shutdown, Installation  
W Warm up



# 2.1 Study, Design, Procurement & Installation

# Design reports


- **Communication** & release of **Official** documents and books is **mandatory** to share pertinent information across the project

## MAX IV design report




2010

## LHC design report



2004

## HL-LHC Preliminary design



2015

# LHC Project

- Defining and understanding the machine parameters impacting the vacuum system was a crucial part of the project

CERN  
CH-1211 Geneva 23  
Switzerland



the  
Large  
Hadron  
Collider  
project

LHC Project Document No.  
**LHC-PM-ES-0002.00 rev.1.1**

CERN Div./Group or Supplier/Contractor Document No.  
**AC/TCP**

EDRS Document No.  
**100513.00 rev. 1.1**

Date: April 8, 1999

## Engineering Specification

### GENERAL PARAMETERS FOR EQUIPMENT INSTALLED IN THE LHC

#### Abstract

A number of design parameters and operational scenarios are used in many documents (Project Notes, Project Reports, Market Surveys, Technical Specifications, etc.) either directly, or for calculating safety margins or defining test procedures for machine components. The present document is a compilation of these parameters with a reference to a document or other sources where more detailed information can be found. Equipment installed in the experimental areas has not been considered.

#### Prepared by :

Paul Cruikshank  
Paul Proudlock  
Germana Riddone  
Roberto Saban  
Rüdiger Schmidt

#### Checked by :

Wolfgang Erdt  
Jean-Pierre Gourber  
Oswald Gröbner  
John Pedersen  
Alain Poncet  
Günther Rau  
Felix Rodriguez-Mateos  
Norbert Siegel  
Graham Stevenson  
Laurent Tavlan  
Carlo Wyss

#### Approved by :

Lyndon Evans  
Paul Faugeras  
Philippe Lebrun  
Pierre Lefèvre  
Thomas Taylor



	Design	
	Nominal	Ultimate
Energy [TeV]	7	
Luminosity [ $\times 10^{34} \text{ cm}^{-2} \cdot \text{s}^{-1}$ ]	1.0	2.3
Current [mA]	584	860
Proton per bunch [ $\times 10^{11}$ ]	1.15	1.7
Number of bunches	2808	
Bunch spacing [ns]	25	
Normalised emittance [ $\mu\text{m} \cdot \text{rad}$ ]	3.75	
$\beta^*$ [m]	0.55	
Total crossing angle [ $\mu\text{rad}$ ]	285	
Critical energy [eV]	44.1	
Photon flux [ph/m/s]	$1 \cdot 10^{17}$	$1.5 \cdot 10^{17}$
SR power [W/m]	0.22	0.33
Photon dose [ph/m/year]	$1 \cdot 10^{24}$	$1.5 \cdot 10^{24}$

# Allow provisions for upgrades!

- There might be always good reasons to upgrade the performance of the machine that you ignore at the time of the design of your project ...

## ISR Luminosity Evolution




Fig 9 ISR luminosity during physics runs. Design luminosity  $4 \times 10^{30} \text{ cm}^{-2} \text{ s}^{-1}$ . First ISR experiment to be completed, R101; maximum luminosity  $1.3 \times 10^{31} \text{ cm}^{-2} \text{ s}^{-1}$  December 1982 -- Highest luminosity achieved for physics (R807)  $1.4 \times 10^{31} \text{ cm}^{-2} \text{ s}^{-1}$

## LEP: Design and Reality

Parameter	Design (55 / 95 GeV)	Achieved (46 / 98 GeV)
Bunch current	0.75 mA	1.00 mA
Total beam current	6.0 mA	8.4 / 6.2 mA
Vertical beam-beam parameter	0.03	0.045 / 0.083
Emittance ratio	4.0 %	0.4 %
Maximum luminosity	16 / 27 $10^{30} \text{ cm}^{-2} \text{ s}^{-1}$	23 / 100 $10^{30} \text{ cm}^{-2} \text{ s}^{-1}$
IP beta function $b_x$	1.75 m	1.25 m
IP beta function $b_y$	7.0 cm	4.0 cm

x 10

x 1.4 / 3.7

Reality better than design (result of many years work)!

S. Myers


- LEP becomes LEP2
- LHC becomes HL-LHC
- ESRF upgrades
- KEKB becomes SuperKEKB
- ...

# Base Line Validation


- Many studies conducted over ~ a decade with experts all around the world, some examples:

Material performance qualification


System performance qualification



R. Cimino, I.R. Collins, *App. Surf. Sci.* 235, 231-235, (2004)




V. Anashin *et al.*, *J. Vac. Sci. Technol. A* 14(4) (1996) 2618



C. Scheuerlein *et al.* *Appl. Surf. Sci.* 172(2001)

See O. Malyshev and R. Cimino lectures

Reference unbaked  
Stainless Steel  
ID 156mm - 5V PU



NEG - activated 250°Cx2h + saturated rectangular - 100 mV PU  
A. Rossi, Proc. Ecloud'04

# Design of components / assemblies

- Design **review** (conceptual, detailed, production readiness ...)
- During LHC procurement, the LHC-VAC group internally reviewed all **technical specifications** and **drawings** :
  - ensure compatibility across the vacuum system
  - allows optimisation across components and performance (standardisation)
  - use quality class (class A, approval circuit after control 1&2)
- **GOLDEN Rule**: **reject components**, including in-kind, which **do not meet VACUUM DESIGN APPROVAL**

- **Do's and don'ts** (just a few important ones from LHC design and experience)
  - No halogenated fluxes
  - No cold demountable joints
  - Helium envelopes are all-metal
  - Joining techniques need to be validated (materials, welding, DT)
  - No dye penetrant testing
  - Minimise thin wall components.
  - Combine RT leak and pressure test of components
  - Decide a policy for cold testing of critical components
  - Keep non-vacuum group manufacturing under control – assign a vac link person
  - Don't allow deliveries until tightness certification is approved
  - Minimise number of welds to be tested in the tunnel
  - Many, many more
  - ...

➔ Technical specification & drawing validation

➔ State of the art material, cleaning methods, procedures

# Spares

- a **spare policy / strategy** shall be defined based on:
  - cost
  - time to recover including building of components
  - failure rate
  - failure probability
  - complexity of the component
  - long term storage of spare
  - In case of accident, does the repair can be done in the shadow of another faulty component ?
  - ...
- Driven by major items and possible events (rupture, beam loss ...)




# Long Shutdown 1 (LS1)

- Main aim : **consolidate the splice interconnection** between superconducting magnets to allow operation at 7 TeV/beam
- Started Feb 2013, Physics resumed April 2015



# Overview of LSS Beam Vacuum Activities

- 148 vacuum sector to re-commission *i.e.* 5.1 km of vacuum system (80 % of the LSS)






# Vacuum Layout


- Define components, produce data based drawings and SCADA systems, ease installation and optimise future intervention (e.g. in radioactive areas)

Item ID	Type	From P	Length	SCOB Start	SCOB End	Name	U	V	A	Status
1067337	VCCLA	1778.583	2.73	13143.8568	13152.8888	VCCLA.4LS.R	0	0	0	INSTALLED
1067372	VNAB	1778.863	3	13152.8888	13152.8888	VNAB.4LS.R	0	0	0	INSTALLED
1067373	VCLL	1778.615	1.85	13152.8888	13153.1188	VCLL.4LS.R	0	0	0	INSTALLED
1067374	VNAB	1778.623	3	13153.1188	13154.1188	VNAB.4LS.R	0	0	0	INSTALLED
1067375	VCLB	1778.223	1.88	13154.1188	13155.0088	VCLB.4LS.R	0	0	0	INSTALLED
1067376	VNAB	1778.343	3	13155.0088	13156.0088	VNAB.4LS.R	0	0	0	INSTALLED
1067377	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067378	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067379	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067380	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067381	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067382	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067383	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067384	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067385	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067386	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067387	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067388	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067389	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067390	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067391	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067392	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067393	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067394	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067395	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067396	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067397	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067398	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067399	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067400	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED

Vacuum layout database




Integration studies




Installation drawings

Item ID	Type	From P	Length	SCOB Start	SCOB End	Name	U	V	A	Status
1067397	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067398	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067399	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED
1067400	VCCB	1778.223	1.88	13156.0088	13166.8888	VCCB.4LS	0	0	0	INSTALLED




New components  
Production & follow up



SCADA

# Infrastructure and Material

- Adapted stores, components, tools and **storage management** are mandatory



# Vacuum Acceptance Tests

• Prior installation **all** (several thousands) **equipment** have been baked and **validated at the surface** before installation in the tunnel:

- functional test
- leak detection
- residual gas composition
- total outgassing rate


➔ Logistics, scheduling, coordinating & official reporting

Equipment for test by LSS sector for L51

Wk open sector	Wk close sector	Wk activate sector	Wk test surface	Year	Building	LSS Sector	Line	Reason/Nature work	Equipment 1	Equipment 2	Equipment 3	Equipment 4
10	11	11	7	2013	n/a	5	ASL2	Blue	Repair 3 VM with NC			
11	12	12	8	2013	113	2	ASR2	Both	NEG Pilot Sector	4 x Modules pilot sector	6 x NEG Coated chambers (already tested)	2 VAZNF+2 VPICA
11	13	14	8	2013	n/a	3	ASL3	Red	Repair 1 VM with NC	2 x VAZNF + 2 x VPICA	1 x VPFA	
11	21	22	8	2013	n/a	5	ASR5	Blue	Repair 2 VM with NC	insert/doigt		
12	13	14	9	2013	113	2	ASL2	Both	TDI New Layout	1 x VAZNF	1 x VPFB	1 x VPFA
12	13	15	9	2013	113	3	IPS	Red	Repair 1 VM with NC	4 x VAZDG (avec VPICA)	2 x VPFA	

The screenshot shows a web interface with a document library for 'Vacuum Reports'. A document titled 'Vacuum acceptance report' is highlighted. The report details include:


- Code Name:** Roman pot ALPHA
- Destination:** B7R1.B
- Code Name:** Roman Pot ALPHA + BMSA
- Destination:** A7L1.R
- Code Name:** Roman Pot ALPHA + BMSA
- Destination:** A7R1.B
- Code Name:** VMAPA
- Destination:** 6L2.B / 6R2.R
- Code Name:** VMSP
- Destination:** 6L2.B
- Code Name:** VCDGC-VCDGD
- Destination:** LSS 4L2 and 4R2
- Code Name:** Echabillon cable BPM
- Code Name:** Ferrite TT2-111R Skyworks
- Destination:** LHC TCTP
- Code Name:** Bellow module for collimator
- Destination:** TCS collimator
- Code Name:** BPM cable
- Destination:** TCTP collimators LHC
- Code Name:** BTVSI.CSL2.B1 & BTVSI.ASL2.B1
- Destination:** point 2
- Code Name:** PT100 cables
- Destination:** TCTP collimators LHC
- Code Name:** PT100
- Destination:** LHC
- Code Name:** PT100
- Destination:** LHC
- Code Name:** TCSF jaw
- Destination:** LHC point 6
- Code Name:** Cycled BPM cables
- Destination:** Roman pot for ATLAS
- Code Name:** Ferrite for VMZSA
- Destination:** LHC, LSS2, LSS5, A4L2, A4R2, A4R3, A4R4, A4L6
- Code Name:** Clidop and CFC jaw bloc
- Destination:** TCS and TCP collimators
- Code Name:** Kapton cable
- Destination:** LHC
- Code Name:** C4S5
- Code Name:** Cycled BPM cables
- Destination:** TCTP collimators
- Code Name:** BPM cables pre-series lot n°2
- Destination:** TCTP collimators LHC









G. Cattenoz *et al.*, IPAC 2014

See G. Bregliozzi lecture

# The LHC beam Vacuum Laboratory in 2012



# Examples of tested parts



# Installation and Quality Control



- Expert teams dedicated to **specific tasks**, logistic included
- Industrial support coordinated by CERN staff

LHC Beam Vacuum Non Conformity tracking system / ESTE 2015  
 LHC Beam Vacuum Non Conformity tracking system

Home  
 Non Conformity Report  
 Non Conformity Status  
 How it works  
 Report Library  
 / ESTE 2015

Welcome to LHC Beam Vacuum Section Non Conformity sharepoint. Purpose of this site is to track all nonconformities found on the LHC machine. For notification of a new nonconformity please use this page.





**How to report a new issue?**  
 1. Go to the Non Conformity Tracking page.



J. Sestak *et al.*, IPAC 2015

## LHC Beam Vacuum Non Conformities status wk11

This report shows the overall status of LHC Non Conformity database. In the charts, please select the data type you are looking for. The data are going to be filtered automatically. In case that the issue details are wanted please see selected issue ID on the sharepoint web: <http://www.cern.ch/est/2015/06/01/nc-tracking/>



# Work Orders

- Allows, **scheduling, coordination**, identification of tunnel activities, control of equipment and fulfil **safety** aspects: electrical lock-out, radiation

**IMPACT** VINCENT BAGLIN | Help | Incident | Request Fulfillment

Search Activities By: TE-VSC-BVO LHC machine

**Work Order Request System - Submit**

Badge No: 46942 Group: [Dropdown]

Machine Affected:  Linac  Leu1  Par  Booster  Sr Ring  Other  Exp Floor  Mis Test

Estimated Duration: [Days] [Hours]

Priority:  Urgent  As Time Permits  Notify for Access  Next Shutdown  Next Access  Scheduled Maintenance

Work Description: [Text Area]

Safety Concerns: [Text Area]

Next Clear

Main Menu Query Request Modify Request

02/04/2002 ARW, Grenoble  
Chihyuan Yao

Operations Group  
Advanced Photon Source

**AR 91831: LSS1 (racks and tunnel)** [Closed]

Responsible: PABLO SANTOS DIAZ (786617/TE-VSC-VSM) Facility: LHC Machine System: V - Vacuum Priority: Next Technical Stop Type: Inspection

Description: Instrumentation inspection along the whole straight section.

**When**

Proposed Date: Duration: 3 Day(s)

Earliest Start: Latest End:

Working Time: Normal: Mon - Fri, 07:30 - 18:00

Scheduled: 13-Mar-2017 to 16-Mar-2017  
Access: 12-Mar-2017 to 17-Mar-2017  
Intervention Period: EYETS-LHC-2016-17 (05-Dec-2016 to 14-Apr-2017)

Granted Working Time: Normal: Mon - Fri, 07:30 - 18:00

**Where**

Locations: 3114 (UJ13) 3136 (UJ17)

Access Points: YCA01-PM15, YCA01-UL14 YCA01-PM15, YCA01-UL16

**Who**

Contact Phone: 164287  
Max Participants: 4  
Presence of Short-term radiation workers: No

**Participants:**

**Material Resource:** Instrumentation Inspection.

**Waste:**

**Constraint:**

**Linked Documents:**

**Hazards**

Activity Hazards:

- None
- Comment:



# Commissioning of a vacuum sector

Usually a **3 weeks** intervention (typical of any baked vacuum system) depending on the sector complexity:

- Venting the sector to air
- Mechanical intervention
- Pumping and leak detection
- Bakeout installation
- Bakeout and NEG activation
- Bakeout removal





# Human error



- Controls are necessary because of **human fallibility**, not incompetence
- Would you take this plane **if there were no check list?**



Airbus A380 cockpit

# Some examples

- A classic: venting or commissioning the **wrong vacuum sector!**
- Exchanging the of a turbomolecular pump **without closing the sector valves** while the pump is connected to the beam vacuum venting several vacuum sectors!
- Activating / baking a vacuum sector under **atmospheric pressure!**
- Pumping down a vacuum sector with **aluminium foils used at blank flange!**



# Check lists



Ops Checksheets

Open Checksheet

Enter Year:

2013

View/Edit Templates

[Help \(Wiki Page\)](#)

Start Up 05/04/2013

Select name from list OR enter forename.surname

Select Name:

E-mail to elog

Due Date	Checkpoint	Status	Notes
-5	Machine Changes Logged : ALL modifications that will affect the machine operation are logged in e-log as "Summary of shutdown changes".	Complete Adrian Johnson	All modifications and works that may affect operation have been logged in elog.
-5			E mail sent with a reminder that Start up
-2	All MPS signals visually checked in Control Room, any faults reported and repaired (excluding Vacuum Valves).	Pending	FE19 ABSB-02 Air Pressure switch fault - SO/HS/Msmall investigatig.
-2	Correctors Powered up and left ON (duration determined by schedule) log any unstable PSUs	Complete Wayne Perkins	email sent CA /BR . 11/04 -SR06A-PC-HSTR-05 Unstable.
-2	STORAGE RING : Vault Searched and PSS Permit confirmed.	Pending	
-2	PTWS : All PTWS relevent to Machine Operation have been Closed out and All Operations Keys accounted for.	Complete Wayne Perkins	
-2	Insertion Devices (incl. Wigglers) Checked out : Powered up, Motion confirmed, Soft limits checked, Valid BURT applied.	Pending	Not Done so far: 05I, 106A, 106B, 106 Phasing unit 101-A, 101B, 112, 115
-1	Cryoplant and O2 Alarm handlers : Check with AR that these are live and functioning.	Complete Wayne Perkins	
-1	Vacuum Valve Test Boxes : All Accounted for.	Pending	email sent SL/ND/PA 10/4
-1	BPM MPS Override Boxes (x3) and BPM Override Red Plugs (x3) : All Accounted for.	Complete Wayne Perkins	
-1	LI & BR tested and Operational	Complete Dave Preest	Tested by Chris Christou 03/11/13 all ok New BURT file created.
-1	Walk round Checks Done : Start Up Walkround Checksheet 1 completed.	Complete Dave Preest	Started, see Walkround Checksheet One 08/04/2013



Ops Checksheets

Open Checksheet

Enter Year:

2013

View/Edit Templates

[Help \(Wiki Page\)](#)

V. Kempson, ARW 2013



# Visual inspection

- Documented inspection tours are needed and avoids potential failures



Someone forgot a tool on an undulator:  
The imprint of it is visible on the Al vacuum chamber!

# 2.2 Operation



# Vacuum Monitoring – Stand-By

- **General** monitoring : check status of components, record of machine status
- Stand-by with **specific duties**: answer to control room request, act on simple intervention, assist expert teams during complicate / delicate interventions
- Stand-by must be **trained** !

CERN  
CH-1211 Geneva 23  
Switzerland



LHC Project Document No.  
CERN Div./Group or Supplier/Contractor Document No.  
**TE/VSC**  
EDMS Document No.  
**1503404**

Date: 11-12-2014

## TE-VSC Procedure

Procedure for the Operation Follow-up of the LHC and Injector Complex Vacuum Systems

### Abstract

This document describes the tools and procedures for the daily follow-up of the LHC and all injector vacuum systems, which are required to guarantee an optimum efficiency of all systems. It is dedicated for use in the new Vacuum Monitoring Room (VMR). Based on the present vacuum control system, a step-to-step procedure is given to survey the status of all machines comprising the LHC and the complete proton and heavy ion injector chain. The majority of the vacuum systems are controlled with PVSS. A table with acronyms can be found in the Annex.

Author:	Checked by:	Approved by:
Eric PAGE, TE-VSC Edgar MAHNER, TE-VSC Ludovic MOURIER, TE-VSC Jose De La GAMA, TE-VSC Germana RIDDONE, TE-VSC	Paul Cruikshank SLs	Paolo Chigiato

Procedures

### Monitoring report

Author: Francois Bellorini Date: 26/09/2014

#### Summary of observations and interventions

Piquet 1: Francois Bellorini Piquet 2: Esa Paju VC: None  
Report type: Monitoring report (Daily) Duration: 1.5 h Status: Closed

#### Action required on machine

Beam V.LHC Ins V.LHC SPS PS Booster LINAC AD ISO

#### Detailed description

**1.1.LHC Insulation vacuum:**  
 1.2.1. LHC cryogenic system logbook:  
 L51 no monitoring required  
 1.2.2. LHC operation logbook:  
 L51 no monitoring required  
 1.3.2. Control of pumping groups and valves:  
 VPGFH.355.4RB.Q  
 VPGFE.201.5RB.Q

### Piquet report

Author: Jose Antonio Somoza Date: 28/08/2014

#### Summary of observations and interventions

Piquet 1: Berthold Jenninger Piquet 2: Jose Antonio Somoza VCR Staff: None  
Report type: Piquet report (Weekly) Duration: 0 h Status: Closed

#### Concerned machine

Beam V.LHC Ins V.LHC SPS PS Booster LINAC AD ISOLDE Other

#### Detailed description

**Important**

Pour faciliter la prise en compte des rapports de piquet dans les statistiques merci de préciser les détails suivants pour chaque intervention dans la mesure du possible :

1. Date d'intervention
2. Heure d'appel de la CCC
3. Machine, zone
4. Equipement concerné, origine du problème
5. Présence d'interlock ou non
6. Type d'intervention (sur place ou à distance)
7. Temps d'intervention & temps de perte faisceaux

To improve the availability of the informations used for the statistics please specify the details below for each intervention if it is possible:

1. Date of intervention
2. Time of CCC call
3. Machine, zone
4. Affected equipment, problem source
5. Interlock
6. Intervention type (on site or remote)
7. Intervention time & beam lost time


No phone call from the CCC. No intervention during the Piquet's week.  
RAS.

Daily and weekly Reports



# SCADA & Alarms


- Software tools are available to help & alert the vacuum expert
- Next generation will integrate predictive behaviour of pressure levels!



1 2 3 4


Date	Time	System Name	Category	Priority	Message	Problem Detection	
28/09	21:45:06	EAU DEMI	LHC	SH5	3584-R -H08	FDED-00070	PRE-ALARME GENERAL INSTALLATION
28/09	23:53:12	EAU DEMI	MEY	378	0378-R -	FSEP-00378	DEFAULT CONDUCTIVITE BASSIN RESERVOIR
30/09	09:20:15	COMPUTER	BTVI41T				Disk problem.
N	11:13:27	COMPUTER	BP1505				User process not running or duplicated. ...
N	11:20:03	EAU DEMI	2001	2001-1	-	FCUM-00007	DEFAULT GENERAL
N	11:24:42	JAPC-MONITORING	SPS-LOGGING				Parameter value not updated
05/04	12:13:59	STEP	MOSBA6_56				DATA ACQUISITION ERROR
24/03	12:55:11	VIDE STRING	SM18	2173-	-	STRING2	DEFAULT VIDE
16/05	14:25:27	COMM TELEPHONE	MEY	513	0513-R -014	RT2-513	DEFAULT REDRESSEUR
19/07	14:48:23	COMM TIM	MEY	104	0104-R -C-0	T_MMD00	DEFAULT FONCTIONNEMENT EQUIPEMENT TIM
09/08	10:38:55	THER CLIM	MEY	513	0513-S -051	CV2-00407	DEFAULT GENERAL
15/08	23:29:13	48KV_5/ST-REDR	LEP4	2460-	-	ESU-EBU/L4	DECLEN. CHARGEUR 48V
12/09	09:03:03	COMM TIM	LHC	SUX3	3532-R -	E_OP-CTCC...	DEFAULT FONCTIONNEMENT EQUIPEMENT TIM
24/09	20:19:28	EAU DEMI	LHC	RI132	2111-	-	FDED-00091
27/09	12:06:29	TARGET	GPSB81_0				FAN T 10 POWER FAULT (380 V)
29/09	21:07:30	EAU GLACEE	LHC	SU1	2180-R -	UHB-101	DEFAULT GENERAL REGROUPE PRODUCTION EAU G...
02/10	08:44:26	SECU FEU	MEY	513	0513-S -201	SFOZIN-00267	DEFAULT CENTRALE DETECTION INCENDIE
N	11:20:59	CTRL-COMPENSAT_1	BE	0861-	-	EMK516/BE	ALARME CONTROLE COMPENSATEUR 1
N	11:21:49	18KV_TABL_EMD2_BE	BE	0861-	-	EMD2/BE	ALARME DEPART 18KV TABLEAU
N	11:21:50	18KV_ST/CONVER_BE	BE	0861-	-	EMD1-2/BE	ALARME DEPART 18KV STATIONS CONVERSION
N	11:22:15	18KV_COMPENSAT_2_BE	BE	0861-	-	EMD214/BE	ALARME COMPENSATEUR 2
02/10	11:22:46	SURVEILLANCE	BLR_USP_BLM187T				BLM187T_BLR_USP_1 not connected (BEAM LO...
N	11:22	Acknowledge	BLR_USP_BLM140T				BLM140T_BLR_USP_1 not connected (BEAM LO...

LHC




# Pressure Follow-Up

- Expert monitoring: check general trends and track / resolve specific issues, follow daily and detailed machine operation



General trends



## Interlocks records

Type	Name	Date	VACSEC.....	Equipment	Sector valve	Short description	Descr
Interlock	VGGSW.122.4L2.C 30th of November 2012	30/11/2012 14:05	A4L2.X	TDL.4L2.C	VGGSW.122.4L2.X	Beamdump of fill 3348 triggered by ALICE BIC	The b which
Interlock	VGGSW.819.5R4.B 10th of September 2012	10/09/2012 21:51	E5R4.B	BWS.5R4.B	VGGSW.819.5R4.B	Beamdump of fill 3053 triggered due to air leak on BWS	The b trigge
Interlock	2nd Interlock VGST.232.7R7.B 26th of August 2012	26/08/2012 22:30	A7R7.B	VGFB.231 & 233.7R8.B	VGST.232.7R7.B	Beamdump of fill 3006 triggered due to sparking on RF fingers	Pressi
Interlock	Interlock VGST.232.7R7.B 26th of August 2012	26/08/2012 02:30	A7R7.B	VGFB.231 & 233.7R8.B	VGST.232.7R7.B	Beamdump of fill 3003 triggered due to sparking on RF fingers	Pressi
Interlock	Interlock VGST.232.7R7.B 16th of August 2012	16/08/2012 16:20	A7R7.B	VGFB.231 & 233.7R8.B	VGST.232.7R7.B	Beamdump triggered by VGFB	Positi
Interlock	Interlock VGGSF.221.1R8.X 20th of July 2012	20/07/2012 02:00	Both VAX in IP8	VGFB.222 & 219.1R8.X	VGGSF.221.1R8.X	Beamdump triggered by VGFB	Positi


Tracking interlocks

Fill by fill monitoring

# Operation Follow-Up: Checking Design


- **Checking** that the system behave **as expected**: example synchrotron radiation induced gas desorption

## First Observation of Synchrotron Radiation: Aug-2010




- Pressure rise during the beam energy ramp

- Dynamic pressure increases with beam current
- $\Delta P = 2 \cdot 10^{-10}$  mbar




## Cleaning Effect under SR

- Arc extremity's vacuum gauges : unbaked Cu and cryogenic beam screen
- Reduction by **2 orders of magnitude** since October 2010





- 2 trends :
  - Room temperature
  - Cryogenic temperature



- Inside the arc, at 5-20 K,  $\Delta P < 10^{-10}$  mbar (i.e. **below detection limit**)
- The photodesorption yield at **cryogenic temperature** is estimated to be  $< 10^{-4}$  molecules/photon


# Beam conditioning

- This is **not a myth** and it is observed in many machines across the world!
- **Your machine** shall behave the same way




E. Al-Dmour, D. Einfeld, IPAC 2011

Average pressure rise in cell C07 normalized to current Vs. beam dose



O. Gröbner. Vacuum 43 (1992) 27-30




C. Herbeaux, Journée thématiques RTVide, décembre 2014

# Beam scrubbing

- **Graphitization** is clearly visible!

LANL



**dipole chamber (SRBM11, 6/20/07)**



**quadrupole chamber (SRQF11)**


Courtesy R. Macek

# Accelerator Fault Tracker

- Big brother is watching you ... for your system health!
- it Pays:
  - Machine availability > 96%
  - X-ray availability > 91 %

Run 2001-4 Downtime by System  
October 31 through December 23, 2001

Scheduled User Time = 1120.0 hours  
User Downtime = 38.5 hours




02/04/2002 ARW, Grenoble  
Chihyuan Yao

Operations Group  
Advanced Photon Source

Run 2001-4 Faults Per Day By System  
October 30 through December 23, 2001

User Beam Days = 46.7




02/04/2002 ARW, Grenoble  
Chihyuan Yao

Operations Group  
Advanced Photon Source




# Fault allocation

## Fault Allocations 2000-2001



SRS, Daresbury

	PS	RF	CONT ROLS	VAC	Cooling	other	BL	refill
APS	>15%	>15%	>10%	>35%	<5%	>10%	>5%	
ELET TRA	>15%	>5%	>10%	<5%	>10%	>5%	>5%	>10%
ESRF	>5%	>20%	>5%	>25%	>15%	<5%	>5%	







E. Park, ARW2013

E. Karantzoulis, 2002

The vacuum system is always a good candidate for fault generator, in particular at the beginning of a project

# LHC Vacuum: Lost Physics and Fault Time

- A thorough consolidation of the vacuum system during LS1 paid!




L. Ponce et al.



# LHC Design Luminosity: 26<sup>th</sup> June 2016

## We reached design luminosity!



# Celebration at the CCC!



# Summary

- The real life of operation **relies on availability**.
- Availability is a **constant concern** during the life of a system.
- **Availability of vacuum system relies on :**
  - Group Expertise (which must be maintained and continued to be developed)
  - New concepts
  - Studies
  - Design
  - Production & installation follow up: Quality Assurance Plan is a must
  - General monitoring / support by stand-by
  - Fill by fill and daily monitoring / support by experts
  - Repair, consolidation and upgrade of the system
- All these activities are based on **many** technical, engineering and scientific **skills which must be available for the project to ensure availability!**

# Some References


- Cern Accelerator School, Vacuum technology, CERN 99-05
- Cern Accelerator School, Vacuum in accelerators, CERN 2007-03
- This school !

## Workshops & conference

- PAC, EPAC, IPAC series available on JACOW web site
- OLAV: Operation of Large Vacuum Systems Workshops
- ARW: Accelerator Reliability Workshops
- WAO: Workshops on Accelerator Operation

**Thank you for your attention !!!**







Typical default, DCUM 3259.3524

Left side

- a) Side view (only from corridor to DUT)
- b) Metallic noise due to loose spring after milling vacuum chamber
- c) RF fingers filling due to broken coating
- d) aperture reduced ?

From Conform


Spring was broken between May and November 2011.



QQBI.26R7 line V2



Beam Screens with MLI and Fibers



Beam screens with soot in tunnel : C19R3



Sector 3-4 incident: soot and superinsulation debris along ~ 6 km !



