

# Large Systems Commissioning

Kirsten Zapfe, DESY  
CAS Vacuum in Accelerators  
Platja D`Aro, May 21, 2006

*Special thanks to O. Gröbner*



**CAS**


THE CERN ACCELERATOR SCHOOL

# Outline


- **Introduction**
- **Pump Down and Leak Check**
- **Components Check**
- **Bake Out**
- **Interlocks/Safety**
- **Cryogenic Systems**
- **First Beam**
- **Concluding Remarks**

# Introduction


- Accelerator vacuum system




# Introduction



# Introduction



# Introduction



# Introduction




# Introduction

## ● Large systems

- length
- number of components
- complexity

## Example

- LEP
  - 27 km circumference
  - ~ 2700 bellows
  - ~ 7000 feedthroughs
  - ~ 2200 pick-up connections
  - ~ 700 gauges
  - 130 sector valves
  - 520 roughing valves
  - 1900 sputter ion pumps
  - 13.000 flanged connections




DESY

TTF/FLASH



# Pump Down and Leak Check

- **Proper fixture of components**
  - loose/fixed points
  - bellows
- **Pressure decay** → first hints for leak
  - check with RGA or pressure rise method
- **Leak Check**
  - gross check  $p < 10^{-4}$  mbar
  - fine check  $p < 10^{-6}$  mbar
    - flanged connections, ceramics, feedthroughs, windows
  - equipment
    - mobile pump station with leak detector/RGA
  - systematic work necessary
  - switch of sputter ion pumps
    - avoid spoiling with He in case of leak




TTF/FLASH

# Pump Down and Leak Check

- Conditioning of vacuum system without beam

- activation of titanium sublimation pumps




HERA

- Observe behavior of pressure

- ➔ repeat leak check if necessary

- activation of NEG pumps



LEP  
O. Gröbner

# Bake Out

## ● System check


- equipment (heaters, thermocouples, cabling)
- functionality → reliable attachment of sensors
- heating process ( $\Delta T/\text{time}$ , ...), automation
- interlock
  - power failure
  - failure of equipment
  - pressure rise/leak

## ● Cooling of critical components

- magnets, monitors, etc.

## ● During bake out

- avoid large temperature gradients
- check movement of components due to heating
- observe pressure for leaks



HERA


# Components Check

## ● Vacuum equipment

- correct allocation
  - components → cables → electronics
  - display on computer
- functionality of pumps, gauges, valves, etc.

## ● Vacuum control

- remote operation of components
- functionality
- add/improve handling options
- modify/integrate additional parameters




Name: 1acc6	Info: GP OK 10.04
Pos: 113.40	Expert
Vent1-Interlock	
P: 3.5e-11	HV on = 4705 V
	<input type="button" value="HV On"/> <input type="button" value="HV Off"/>
	Permit HV: ON
	<input type="button" value="On"/> <input type="button" value="Off"/>
	Auto off: ON
	<input type="button" value="On"/> <input type="button" value="Off"/>
SEDAC: 3 11 96	


TTF/FLASH

# Components Check

- **Movable elements**  
(collimators, diagnostics, ...)
  - correct path length
  - end switches
  - remote operation
    - ➔ check for pressure increase during movements
- **Special equipment of experiments**
  - e.g. gas inlet systems
- **Final alignment**
  - be careful shifting components under vacuum
    - ➔ temporarily unfixed components



HERA-B




# Interlocks/Safety Checks

- **Self safe operation of system**
  - failing of equipment (pumps, gauges)
- **Vacuum interlocks → closing of valves**
  - pressure increase
  - failing of equipment (pumps, gauges)
  - switching off equipment
- **Fast shutters/delay lines**

**prepare adequate tools for  
check-out in advance**

TTF/FLASH



# Interlocks/Safety Checks

- **Beam interlocks**

- linear accelerator → stop beam production
- storage rings → dump beam


- **Different modes of beam operation**

- injection
- user beam lines

- **Interlocks connected to other systems**


- diagnostics
- experiments

TTF/FLASH




# Cryogenic Systems

- **Superconducting magnets**
  - beam pipe partially surrounded by liquid helium  
e.g. Tevatron, HERA, RHIC, LHC



HERA







# Cryogenic Systems

- **Superconducting accelerating structures (cavities)**

- cavities = beam pipe surrounded by liquid helium  
e.g. Tristan, LEP, CEBAF, TTF/FLASH, XFEL, ...



TTF, XFEL




LEP

- **Special insertions for superconducting wigglers, experiments etc.**

# Cold Beam Vacuum Systems

- **Leak check of final connections**


- flanges, in-situ welds
- no leak check under cold conditions possible
  - extreme care necessary, e.g. integral leak check



LHC

# Cold Beam Vacuum Systems

- **Pressure before cool down**
  - permanent pumps (e.g. sputter ion pumps)
    - HERA:  $p \sim 10^{-6}$  mbar
  - no active pumping after pump down
    - RHIC  $p < 10^{-2}$  mbar





HERA

# Cold Beam Vacuum Systems

- **Cool down**

- beam pipe = cryo pump → pressure drop



HERA  
RT → 4.5 K

- **Measure integral leak rate and wall coverage**

- release of gas during warm up measured with RGA

# Insulating Vacuum Systems

## ● Segmentation


● distance of vacuum barriers has increased with time

- HERA → 20 m
- RHIC → 500 m
- LHC → 200 m


→ larger distance = increased complexity for commissioning

### LHC ARC: CRYOGENIC AND INSULATION VACUUM BASELINE DESIGN

#### Insulation Vacuum sectorization:



#### Cold-mass sectorization:



# Insulating Vacuum Systems



- **Pump down**

- equipment

- start with large roughing pumps
- sufficient mobile pump stations necessary

- initial pump down dominated by large amounts of water from super insulating foils

- be prepared for frequent maintenance of roughing pumps
- eventually flushing with N<sub>2</sub>



HERA

TTF/XFEL

# Insulating Vacuum Systems

## Example




Fig. 6 Pumpdown Curves of RHIC 494m Arc Cryostats


RHIC  
D. Hseuh et al.

**first pump down takes a long time**

# Insulating Vacuum Systems

## ● Leak check of air leaks

- equipment → sufficient granularity important
  - leak detectors at mobile pump stations and/or directly attached to tank
    - base pressure usually not sufficient for RGA
  - gauges
- He background in tunnel may be significant
  - leaks from cryogenic He supply lines
  - no exhaust line for roughing pumps
    - HD as alternative to He as tracer gas
- dead time could be significant
- large leaks are not exceptional
  - at high pressure small leaks are not detectable
  - needs to repair large leaks first
    - repeat complete leak check






# Insulating Vacuum Systems

## ● Leak check of air leaks (cont'd)

### ● O-rings

- permeation determines detection limit for leaks
- permeation takes time
  - ➔ might simulate leak due to delay in signal



C. Falland (DESY), unpubl.

# Insulating Vacuum Systems


- **Leak check of process lines**

- equipment

- same as for leak check of insulating vacuum
  - ↳ leak detectors/gauges
- sufficient He compression in case of He leaks necessary

- with insulating vacuum pumped down

- pump out process lines
  - ↳ background level
- pressurize one line after the other
  - e.g. HERA: 15 bar He



LHC

# Insulating Vacuum Systems

## ● Leak check of process lines (cont.)

### ● leak location

- often not easy to find
  - ➔ sufficient diagnosis mandatory
  - ➔ profile of He signal
- vent insulating vacuum, open sliding sleeves, check welds, etc.
  - ➔ pressurized with sniffer
  - ➔ pressurized with vacuum tight fixtures

**locating and repairing He leaks -  
difficult and time consuming effort**

RHIC/ D. Hseuh et al.







Fig. 7 Helium Pressure Gradients at Interconnects in 494m Arc Cryostats



# Insulating Vacuum Systems

## ● Cool down

- check for movement of components due to shrinkage of materials
- pressure drop
  - $10^{-3}$  mbar required before cool down
  - $10^{-6}$  mbar required for routine operation
    - ➔ remove part of mobile pump stations
- check for condensation/freezing of water
  - thermal bridges
- monitoring of He signal
  - leaks from process lines
    - ➔ locate after warm up
    - ➔ cold leaks



HERA  
4.5 K

# Insulating Vacuum Systems

- **Leaks which can not be localized or repaired**

- He leaks

- inside magnets, cavities, ...


- add pump stations at insulating vacuum

- air leaks


- flanges on insulating tanks, ...

- glue, rubber mastic ...

HERA  
4.5 K



a) Normal distribution of pump stations and valves open



b) Additional pump station at leaky section

# Insulating Vacuum Systems

- **Observe also beam vacuum**

- during leak check of process lines
- during cool down

- ➔ **direct leaks from (liquid) He at sc. cavities/ sc. Magnets**
- ➔ **leaks against insulating vacuum**
- ➔ **combined leaks:  
process lines**

➔ **insulating vacuum**

➔ **beam vacuum**

- less critical if leak against insulating vacuum
- not so nice ➔ He leaking into beam vacuum
  - ➔ supply sufficient pumping speed for He
  - e.g. sputter ion pump with enhanced He pumping speed
  - e.g. charcoal (RHIC)




# First Beam

- **First passage of beam ...**


**... possible reasons if the beam does not pass**

- closed valves
  - obstacles, e.g. rf fingers
  - ...
  - proper functioning of magnets, etc.
- **Check heating of components**
    - proper rf-shielding
    - proper cooling (synchrotron radiation)



# First Beam


- **Beam life time**
- **Beam-gas effects**
- **Pressure behavior**
  - thermal heating
  - photon-induced desorption
- **Conditioning of vacuum with beam**
  - cleaning of surface → beam scrubbing



LEP  
O. Gröbner



# Concluding Remarks



- **Sufficient time for systems tests necessary**

- installation of vacuum system is one of the final steps of accelerator installation
- time slot often reduced due to delays of preceding steps
- pump down can not really be speed up

**proper planning of commissioning  
=  
part of vacuum system planning**



Courtesy to A. de Zubiaurre Wagner